

## KANCHRAPARA COLLEGE

Kanchrapara, North 24-Parganas Pin – 743 145 Ph. No. 2585 8790 2585 5159

E-mail -<u>info@kpcoll.ac.in</u> ESTD - 1972

website: http://www.kanchraparacollege.ac.in

Ref. No.: KPC/PC/Tender/Room 12/tiles/2022-247

Date: 18: 7: 22.....

## NoticeInvitingTender

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender )capability for execution of works as depicted hereunder for participating in the tender.

SI N	1	Name of the work	Estimated amount put to tender (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
	1	" PROPOSED ESTIMATE OF FLOOR TILES WORK FOR ROOM NO 12	259037	5181	

Last date of submission of	01.08.2022, 2P.M.					
Tender/quotation paper						
Place of receipt of Quotation	Tender Box, Front of Principal Chamber					
Time and date of opening of Quotation	04.08.2022, 3P.M.					
Place of opening of Quotation	Principal Chamber					

- Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
- 3. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
- 4. The quotation documents are not transferable.
- 5. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal 8 7 /22

Kanchrapara College
Kanchrapara, 24 Pgs (N)

## PROPOSED ESTIMATE OF FLOOR TILES WORK FOR ROOM NO 12 OF KANCHARAPARA COLLEGE AT HOLDING NO -2, SIRAJ MONDAL LANE WORDNO - 8, KANCHARAPARA , J.L NO-2, MOUZA- BAHIRBAG, P.S-BIJPUR, PLOT NO- 1616,1627,1632,1635, KHATIAN NO- 2585, UNDER KANCHARAPARA MUNICIPALITY, PIN-713145, DIST- NORSTH 24 PARGANAS

il. Io	Decription of Item	No of floor	no	length (M)	Breath (M)	Height (M)	У	Unit	Rate Rs.	Amount Rs
_	Stripping off worn out plaster and raking out joints of walls,		1	18.92	6.75		127.71	-		
	cellings etc. upto any height and in any floor including		1	0	0		0			
2	removing rubbish within a lead of 75m as directed.					0.1	0	-+		
		1			Total	0.1	127.71		19.00	2426.49
3	Supplying, fitting, fixing marble slab/tiles, 15 mm. to 18 mm. thick in dado / wall in 15 mm thick [avg] cement mortar (1:2) ncluding making suitable arrangements to hold the stones properly by brass / copper hooks applying white cement slurry @ 4.4 kg/ sq.m at the back side of marble & pointing in cement mortar (1:2) (1 cement, 2 marble dust) with admixture of pigment matching the stone shades including polishing all complete as per direction of the Engineer-in-charge		floo	18.92	2 6.75		127.71			
	including cost of materials, labours, scaffolding, staging,	1	+ •	1 0	1 0		127.71	SQM	1792.00	228856.32
	curing					Total			Rs Rs	231282.81 27753.94
	Add G.S.T 12%							4625.66		
	Add contingency 2 % Rs							2590.37		
Add Cess 1% Final Estimate Amount Rs							266252.77			
	Say Rs								s 266253.00	

Signature of Owner: -

Principal College
Kanchrapara, 24 Pgs (N)

MANOJ MARIRI Diploma Civil Engineer Reg. No.-61633 (ICE (I))