

KANCHRAPARA COLLEGE

Kanchrapara, North 24-Parganas Pin - 743 145

Ph. No. 2585 8790 2585 5159

E-mail -info@kpcoll.ac.in ESTD - 1972

website: http://www.kanchraparacollege.ac.in

Date: 21/7/2021

Ref. No.: KOC/OC/Tander/Shee/2011-264

Notice Inviting Tender

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under Kanchrapara College Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. N		Name of the work	Estimated amount put to tender (in Rs.)	Earnest Money 2% of Estimate Amount (in Rs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (in Rs.)
	1	PROPOSED ESTIMATE OF CONSTRUCTION OF MODEL STACHU SHED	417249	8344	

Last date of submission of	28.07.2022, 2P.M.		
Tender/quotation paper			
Place of receipt of Quotation	Tender Box, Front of Principal Chamber		
Time and date of opening of Quotation	29.07.2022, 3P.M.		
Place of opening of Quotation	Principal Chamber		

- 2. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
- 3. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
- 4. The quotation documents are not transferable.
- 5. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Kanchrapa & College Kanchrapara, 24 Pgs (N) OSED CONSTRUCTIONOF MODEL STACHU SHED IN FRONT OF KANCHRAPARA COLLAGE AT NG NO - 2, SIRAJ MOMDAL LANE, WARD NO - 8, MOUZA - BAHIRBAG, PLOT NO - 1616,1627,1632, OTIAN NO-3585, JL NO-2, UNDER KANCHRAPARA MUNICIPALITY, DIP 743145, DIST - NORTH 24 PARGANAS.

	SCHEDUL	SCHEDULE OF COSTING AS PER PWD RATE							
1	Description of Items	Uon	A THEORY & SALE		Amount	Rem			
	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete.	Cum	0.75	119.27		89			
\vdash	Cement concrete with graded jhama khoa (30 mm size) excluding shuttering In ground floor and foundation (a) 1:3:6 proportion	Cum	1.80	4757.00	ε	3,563			
3	Controlled Cement concrete with well graded stone chips (20 mm nominal size) excluding shuttering and reinforcement with complete design of concrete as per 1S: 456 and relevant special publications, submission of job mix formula after preliminary mix design after testing of concrete cubes as per direction of Engineer-in charge. Consumption of cement will not be less than 300 Kg of cement with Super plasticiser per cubic meter of controlled concrete but actual consumption will be determined on the basis of preliminary test and job mix foumula. In ground floor and foundation. [using concrete mixture] [b] M 25 Grade with Pakur Variety	Cum	10.58	5503.00	58	3,241			
4	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out aftercompletion of works (upto roof of ground floor) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge.	Sqm	92.72	351.00	32,546	, /			
	S Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. I. SAIL/ TATA/RINL	МТ	0.60	58103.00	34,860				
	Brick work with 1st class bricks in cement mortar (1:4), In superstructure, ground floor	Cum	4.11	5267.00	21,653				
	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface With 1:4 cement mortar								
		Sqm	26.25	172.00	4,515				
	(110	Sqm Sqm	0.00	164.00 122.00		$\overline{}$			
	Supplying, fitting and fixing Marble Slab/tile of 15 to 18 mm thickness in floor, lobby, stair, landing & treads etc. over 20 mm (av.) thek base of Cement mortar (1:2) laid with white cement slurry @ 4.4 kg/Sq.m before placing marble & jointed	gm	9.76	1902.00	18,564				

		X	P-mail · nri-	de la .		
	ying, fitting and fixing Marble Slab/tile of 15 to 18 mm kness in floor, lobby, stair, landing & treads etc. over 20 mm (av.) thck base of Cement mortar (1:2) laid with white cement slurry @ 4.4 kg/Sq.m before placing marble & jointed with white cement slurry @ 2.0 kg/Sq.m with necessary pigments including grinding and Granite polishing as per direction of Engineering -in -Charge in Ground Floor. { white cement and Pigment to be supplied by the Agency}, { white cement and Pigment to be supplied by the Agency}.	Sqm	50.08	2466.00	1,23,485	
10	(iv) Area of each state of executed on specific permission of Superintending of executed on specific permission of Superintending of executed on pecific permission of Superintending of executed on specific permission of Superintending of Executed Ones (Superintending o	Sqm	146.00	101.00	14,746	The Comments of the Comments o
11	Emulsion. Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothning of surface.	Sqm	146.00	76.00	11,096	
12	Two Coats Fitting fixing 8"/4" concrete artificial decorativ roof tiles, fitting with sand cemont morter including painting (asbestas style ar tradisanal roof tilse style) (according to market prise	no	1050.00	22.00	23,100 3,51,457	
			TOTAL =		21,087	7
					10,544	1:
13	Add 6% Cost for Electrification Add 3% Cost for Contingencies	PROJECT COST = 372545			3,83,089	1:
E	Add 6% for C.G.S.T			22332 24252 24249	22,985.32 - 22,985.32 - 4,29,059.27	
1	Add 6% for S.G.S.T	-	IOTAL	Say 417240	4,29,059.00	

(Rupess Four Lakhs Tweenty Nine Thousand Fifty Nine Only)

Signature of Owner: 22/07/2022

Estimatted By

MANOJ MISTAL Diploma Civil Engineer Reg. No.-61633 (ICE (I))

Principal Kanchrapara College Kanchrapara, 24 Pgs (N)